

PREMIER ROOFING SOLUTIONS LLC

May 5, 2024

Mike Campbell
Weiser Library
628 E. 1st Street
Weiser, ID 83672

Dear Mike,

Specifications and estimate for roof restoration system on approximately 8,600 square feet which includes the following:

1. Prep roof as needed.
2. Power wash roof to remove dirt, debris and existing silicone.
3. Apply Inland RC 2250 poly urethane seam sealer on all seams and penetrations as recommended.
4. Apply 36" reinforcement fabric in water carrying areas and around drains. (170 lf of 36" fabric).
5. Apply Inland RC 1800 high solids over entire surface at a rate of 2.25 gallons per 100 square feet for a 20-year system.
6. Detail roof.
7. Install new blocking under conduit.
8. Install new drain covers as needed.

Total price \$32,919.00

Standard 5-year labor warranty and a 20-year material warranty.

In lieu of the standard warranty, there is an optional manufacture 20-year labor, and material warranty would be an additional \$2,000.00.

**Exclusion for the manufactures 20-year labor and material warranty is that if the existing coating delaminates is excluded.

If you have any questions, please feel free to give me a call at 208-230-3408.

Respectfully,

Daren Schuster
Member

549 Jacobsen Gulch Road
Ontario, OR 97914
208-230-3408

premierroofingsolutions21@gmail.com
License OR 240175 ID RCE-61315